

Stewart Building  
North Washington Street  
Easton, Maryland 21601

T-26  
C1810  
With Later Alterations

The "Old Brick Hotel" as this building is commonly known, was probably constructed soon after a big fire of 1808. A Federal period building, its earliest appearance is unknown, but the structure must have been an L-shaped corner building, two-and-a-half stories high with a gable roof and dormers. Flat keystone window arches and a Flemish bond facade are the major details remaining from this period. By the mid nineteenth century, photographs show a mansard roof with elegant cast iron cresting. Tudor revival elements - beaded glass windows and parapet roofs - were added in the 1920's. Used as a hotel for many years, the building now houses apartments and shops.

## MARYLAND HISTORICAL TRUST

T 26  
2100264311  
Town of Easton

## INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

**1 NAME**

HISTORIC

Old Brick Hotel

AND/OR COMMON

Stewart Building

**2 LOCATION**

STREET &amp; NUMBER

CITY, TOWN

CONGRESSIONAL DISTRICT

\_\_\_ VICINITY OF

STATE

COUNTY

**3 CLASSIFICATION**

## CATEGORY

\_\_\_DISTRICT

☒ BUILDING(S)

\_\_\_STRUCTURE

\_\_\_SITE

\_\_\_OBJECT

## OWNERSHIP

\_\_\_PUBLIC

☒ PRIVATE

\_\_\_BOTH

## PUBLIC ACQUISITION

\_\_\_IN PROCESS

\_\_\_BEING CONSIDERED

## STATUS

☒ OCCUPIED

\_\_\_UNOCCUPIED

\_\_\_WORK IN PROGRESS

## ACCESSIBLE

☒ YES: RESTRICTED

\_\_\_YES: UNRESTRICTED

\_\_\_NO

## PRESENT USE

\_\_\_AGRICULTURE

\_\_\_MUSEUM

☒ COMMERCIAL

\_\_\_PARK

\_\_\_EDUCATIONAL

\_\_\_PRIVATE RESIDENCE

\_\_\_ENTERTAINMENT

\_\_\_RELIGIOUS

\_\_\_GOVERNMENT

\_\_\_SCIENTIFIC

\_\_\_INDUSTRIAL

\_\_\_TRANSPORTATION

\_\_\_MILITARY

\_\_\_OTHER

**4 OWNER OF PROPERTY**

NAME

Anne N. B. Lockhart

Telephone #: 301-822-4098

STREET &amp; NUMBER

Box 613

CITY, TOWN

Easton

\_\_\_ VICINITY OF

STATE, zip code

Maryland 21601

**5 LOCATION OF LEGAL DESCRIPTION**COURTHOUSE,  
REGISTRY OF DEEDS, ETC.

Talbot County Court House

STREET &amp; NUMBER

Washington Street

CITY, TOWN

Easton

STATE

Maryland 21601

**6 REPRESENTATION IN EXISTING SURVEYS**

TITLE

Town of Easton Survey by Paul Brinkman

DATE

August 28, 1967

\_\_\_FEDERAL ☒ STATE \_\_\_COUNTY \_\_\_LOCALDEPOSITORY FOR  
SURVEY RECORDS

Maryland Historical Trust

CITY, TOWN

Annapolis

STATE

Maryland

# 7 DESCRIPTION

## CONDITION

— EXCELLENT  
☒ GOOD  
 — FAIR

— DETERIORATED  
 — RUINS  
 — UNEXPOSED

## CHECK ONE

— UNALTERED  
☒ ALTERED

## CHECK ONE

☒ ORIGINAL SITE  
 — MOVED      DATE \_\_\_\_\_

## DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

The Stewart Building, also known as the Old Brick Hotel, is an L-shaped corner building, seven bays long on North Washington Street and eight bays long on Federal Street.

It is a two-and-a-half story high with a Mansard roof. The Mansard is covered with wooden shingles with alternating rows of imbricated and butt-ended shingles. Dormers pierce the roof; the three dormers on the Federal Street side occur between bays. Two dormers, one with a single window, are used on the east slope. Each has eight-light casement windows with flat lead comes and is covered by a shallow gable roof.

On the Federal Street facade a Tudor-revival facade has been inserted into the third bay from the corner. It has a wide window opening with casements on the upper floor and an ornamental parapet. Recessed windows are placed between remaining dormers, one on each facade. Each has five casement windows.

Second floor windows are evenly spaced on both facades; six over six sashes are used. On the south facade the lintels are flat and unmolded. Plain sills project slightly from the brick surface. On the east, windows have double keystone lintels of sandstone. These are set flush and are decorated with the carving used in several of the Washington Street Federal buildings.

Now used as stores, the first floor has Tudor-revival details - narrow, leaded casement windows and central entrance doors. The plate glass windows of a men's clothing store occupy the east - Washington Street - facade and the eastern bays of the south facade. The corner entrance to this store has transom lights with twenty small panes and a simple entrance door.

The upper floors are reached by an entrance on the south facade. Used as offices, these floors have twentieth-century details.

The brick facade of the building gives a hint of its evolution. Originally constructed about 1818, the structure has the Flemish bond brick-work common to buildings of the early nineteenth century. Portions of the wall have been repaired - some carelessly in common bond; others are relaid Flemish bond but with machine-made bricks. Alterations in the brick can also be seen above several windows where sandstone lintels have been removed.

The structure was built as a hotel. No photographs of its earliest appearance survive, but it may have had a gable roof with dormers and six over six windows. The Mansard roof must have been added in the mid-nineteenth century. Old photographs show it to have been an extremely handsome building with an elegant cast iron cresting on the roof. Shutters were used at each window. Keystone lintels were painted on the south facade. The entrances were in their present location; the corner entrance being covered with round arched openings. Narrow balconies several feet wide with slender, turned balusters were used above the Federal Street entrance and on the east facade. A square lantern, probably of brass, hung at the corner.

In the 1920's the Tudor-revival details were added and the building connected to its western neighbor on Federal Street.

Despite its many alterations, this interesting structure is attractive and well maintained. The east facade and first floor on the south is painted light green; trim is a darker green.

CONTINUE ON SEPARATE SHEET IF NECESSARY

# 8 SIGNIFICANCE

PERIOD	AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW				
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION	
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE	
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE	
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE	<input type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN	
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER	
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION	
<input type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)	
		<input type="checkbox"/> INVENTION			

SPECIFIC DATES      C1810

BUILDER/ARCHITECT      Samuel Groome

## STATEMENT OF SIGNIFICANCE

The building is significant for its architecture. It is one of the town's earlier buildings, constructed during the Federal period. With its attractive dark-red brick work and elegant sandstone lintels, it must have been a distinctive building that turned the corner between the row of fine Federal buildings to the north and the Georgian Court House across Federal Street.

In the second phase, it was one of the finest of Easton's Victorian buildings, restrained and well proportioned, with finely crafted wrought iron cresting and brass lantern. The Mansard roof remains one of Easton's best examples of the decorative single roofs used at the time.

In its present condition the building is an example of the fanciful Tudor-revival of the 1920's with its penchant for leaded glass, round openings and parapet roofs.

L34/F588

In 1811, William Groome bought a lot of ground on "Federal Alley" and the west side of Washington Street for \$400.00. Along Federal Alley directly north of the Court House, there had been earlier buildings, taverns, stables, and such. But a fire swept the corner in 1810 and Mr. Groome picked up the wreckage at a cheap price. He immediately set about building a good-sized brick hotel-tavern, probably the earliest hotel in the community. The establishment remained in the hands of Samuel Groome and his heirs until 1853, when Col. Samuel Hambleton, one of the town's leading attorneys, bought the property and continued to run it as a hotel. His heirs sold it in 1893 to the Moreland Improvement Co. of Talbot County. It ceased to function as a hotel about this time. In 1927, the Isla Corporation paid \$40,500.00 for the holdings. One more owner came along in 1965 until the present one, Mrs. Anne N. B. Lockhart who purchased it in 1969.

L65/F162

L120/F169

L208/F445

L432/F653

CONTINUE ON SEPARATE SHEET IF NECESSARY

**9 MAJOR BIBLIOGRAPHICAL REFERENCES**

Deeds and Land Records, Talbot County Court House.

Garey, George and Ellwood Patchett. History of Easton, (Easton, Maryland: Gazette Steam Book for Job Offices), 1881. Reprinted by Historic Easton, Incorporated, January 1974.

Photographs in the collection of the Maryland Room of the Talbot County Free Library.

(cont.)

CONTINUE ON SEPARATE SHEET IF NECESSARY

**10 GEOGRAPHICAL DATA**

ACREAGE OF NOMINATED PROPERTY NA

VERBAL BOUNDARY DESCRIPTION

NA

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE None COUNTY

STATE COUNTY

**11 FORM PREPARED BY**

NAME / TITLE

Marsha L. Fritz, Consultant Cynthia B. Ludlow, Research Historian

ORGANIZATION

Historic Easton, Incorporated

DATE

October 1, 1976

STREET & NUMBER

Box 1171

TELEPHONE Mr. Paul Parsons,

301-822-2706 President

CITY OR TOWN

Easton

STATE

Maryland 21601

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust  
The Shaw House, 21 State Circle  
Annapolis, Maryland 21401  
(301) 267-1438

T-26  
North Washington Street  
Easton, Maryland 21601

Old Brick Hotel  
Stewart Building

(9) Major Bibliographical References

Mulliken, James C. A History of Easton Volunteer  
Fire Department. (Easton, Maryland: 1962).

Form 10-300  
(Dec. 1968)UNITED STATES DEPARTMENT OF THE INTERIOR  
NATIONAL PARK SERVICENATIONAL REGISTER OF HISTORIC PLACES  
INVENTORY - NOMINATION FORM

(Type all entries - complete applicable sections)

STATE:	
COUNTY:	
FOR NPS USE ONLY	
ENTRY NUMBER	DATE

<b>1. NAME</b>			
COMMON: No. 10 Federal Street (Old Brick Hotel)			
AND/OR HISTORIC: (Part of Stewart Building).			
<b>2. LOCATION</b>			
STREET AND NUMBER: 10 Federal Street (Counthouse Square)			
CITY OR TOWN: Easton			
STATE: Md.		CODE	COUNTY: Talbot
<b>3. CLASSIFICATION</b>			
CATEGORY (Check One)		OWNERSHIP	STATUS
District <input type="checkbox"/> Building <input checked="" type="checkbox"/> Site <input type="checkbox"/> Structure <input type="checkbox"/> Object <input type="checkbox"/>		Public <input type="checkbox"/> Private <input checked="" type="checkbox"/> Both <input type="checkbox"/> Public Acquisition: In Process <input type="checkbox"/> Being Considered <input type="checkbox"/>	Occupied <input checked="" type="checkbox"/> Yes: Unoccupied <input type="checkbox"/> Restricted <input checked="" type="checkbox"/> Preservation work in progress <input type="checkbox"/> No: <input type="checkbox"/>
PRESENT USE (Check One or More as Appropriate)			
Agricultural <input type="checkbox"/> Commercial <input checked="" type="checkbox"/> Educational <input type="checkbox"/> Entertainment <input type="checkbox"/>		Government <input type="checkbox"/> Industrial <input type="checkbox"/> Military <input type="checkbox"/> Museum <input type="checkbox"/>	Park <input type="checkbox"/> Private Residence <input type="checkbox"/> Religious <input type="checkbox"/> Scientific <input type="checkbox"/>
Transportation <input type="checkbox"/> Other (Specify) <input type="checkbox"/>		Comments <input type="checkbox"/>	
<b>4. OWNER OF PROPERTY</b>			
OWNERS NAME:			
STREET AND NUMBER:			
CITY OR TOWN:		STATE:	CODE
<b>5. LOCATION OF LEGAL DESCRIPTION</b>			
COURTHOUSE, REGISTRY OF DEEDS, ETC.:			
STREET AND NUMBER:			
CITY OR TOWN:		STATE:	CODE
APPROXIMATE ACREAGE OF NOMINATED PROPERTY:			
<b>6. REPRESENTATION IN EXISTING SURVEYS</b>			
TITLE OF SURVEY:			
DATE OF SURVEY: Federal <input type="checkbox"/> State <input type="checkbox"/> County <input type="checkbox"/> Local <input type="checkbox"/>			
DEPOSITORY FOR SURVEY RECORDS:			
STREET AND NUMBER:			
CITY OR TOWN:		STATE:	CODE

SEE INSTRUCTIONS

FOR NPS USE ONLY  
ENTRY NUMBER  
DATE

## 7. DESCRIPTION

CONDITION	(Check One)					
	Excellent <input type="checkbox"/>	Good <input checked="" type="checkbox"/>	Fair <input type="checkbox"/>	Deteriorated <input type="checkbox"/>	Ruins <input type="checkbox"/>	Unexposed <input type="checkbox"/>
INTEGRITY <sup>2</sup>	(Check One)			(Check One)		
	Altered <input type="checkbox"/>	Unaltered <input type="checkbox"/>	Moved <input type="checkbox"/>	Original Site <input checked="" type="checkbox"/>		

DESCRIBE THE PRESENT AND ORIGINAL (If known) PHYSICAL APPEARANCE

No. 10 Federal Street is part of ~~the~~ 3 story\* red brick block known as the Stewart block, the western part of which is a 1928 copy of the eastern section. No 10<sup>would</sup> appear to have \*(3rd story mansard roof, probably later than rest of early part of Stewart Building) been created from the older section (?), but it is 3 stories which the 3rd story projecting over 2d, and 2nd projecting well over entrance and bay window - no. on to form an entrance porch. ~~Continuation of~~ 2nd + 3rd stories show an English half-timber facade with brick nogging. 3rd floor has 4 bas-relief concrete (after) plaster panels showing 4 tree motifs. All windows are of the casement type, and bay windows have lead mullions.

SEE INSTRUCTIONS



## 8. SIGNIFICANCE

PERIOD (Check One or More as Appropriate)

Pre-Columbian ☐16th Century ☐18th Century ☐20th Century ☒15th Century ☐17th Century ☐19th Century ☐

SPECIFIC DATE(S) (If Applicable and Known)

(1815 early hotel)

AREAS OF SIGNIFICANCE (Check One or More as Appropriate)

Aboriginal ☐Education ☐Political ☐Urban Planning ☐Prehistoric ☐Engineering ☐

Religion/Phi-

Other (Specify) ☐Historic ☐Industry ☐losophy ☐ArchitectureAgriculture ☐Invention ☐Science ☐Art ☐Landscape ☐Sculpture ☐Commerce ☐Architecture ☐

Social/Human-

Communications ☐Literature ☐itarian ☐Conservation ☐Military ☐Theater ☐Music ☐Transportation ☐

STATEMENT OF SIGNIFICANCE (Include Personages, Dates, Events, Etc.)

\* 10 Federal Street is an attempt at creating the effect of an English west country half-timbered house (e.g. 15th c. Shrewsbury & Ludlow in Shropshire) - early English urban commercial. Fantastic & rare example of creative eclecticism of early 20th c., influenced - helped by use of English models for academic audit. - Purinton had 2 houses in this 1/2 timbered style - 1 still standing

SEE INSTRUCTIONS

## 9. MAJOR BIBLIOGRAPHICAL REFERENCES

## 10. GEOGRAPHICAL DATA

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY			O R	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN ONE ACRE		
CORNER	LATITUDE	LONGITUDE		LATITUDE	LONGITUDE	
	Degrees Minutes Seconds	Degrees Minutes Seconds		Degrees Minutes Seconds	Degrees Minutes Seconds	
NW	° ' "	° ' "		° ' "	° ' "	
NE	° ' "	° ' "		° ' "	° ' "	
SE	° ' "	° ' "		° ' "	° ' "	
SW	° ' "	° ' "		° ' "	° ' "	

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE:	CODE	COUNTY	CODE
STATE:	CODE	COUNTY:	CODE
STATE:	CODE	COUNTY:	CODE
STATE:	CODE	COUNTY:	CODE

## 11. FORM PREPARED BY

NAME AND TITLE: <i>WDM</i>		
ORGANIZATION: <i>NHT</i>	DATE: <i>Jan 12, 1969</i>	
STREET AND NUMBER:		
CITY OR TOWN:	STATE	CODE

## 12. STATE LIAISON OFFICER CERTIFICATION

## NATIONAL REGISTER VERIFICATION

As the designated State Liaison Officer for the National Historic Preservation Act of 1966 (Public Law 89-665), I hereby nominate this property for inclusion in the National Register and certify that it has been evaluated according to the criteria and procedures set forth by the National Park Service. The recommended level of significance of this nomination is:

National ☐ State ☐ Local ☐

Name \_\_\_\_\_

Title \_\_\_\_\_

Date \_\_\_\_\_

I hereby certify that this property is included in the National Register.

\_\_\_\_\_  
Chief, Office of Archeology and Historic Preservation


Date \_\_\_\_\_


ATTEST:

\_\_\_\_\_  
Keeper of The National Register

Date \_\_\_\_\_

SEE INSTRUCTIONS

1. STATE <b>Maryland</b> COUNTY <b>Talbot</b> TOWN <b>Easton</b> VICINITY STREET NO. <b>Washington &amp; Federal Sts</b>  ORIGINAL OWNER ORIGINAL USE <b>Hotel</b> PRESENT OWNER PRESENT USE <b>Shops and dwellings</b> WALL CONSTRUCTION <b>Flemish bond brick</b> NO. OF STORIES <b>three</b>		HISTORIC AMERICAN BUILDINGS SURVEY INVENTORY  2. NAME <b>Old Brick Hotel</b>  DATE OR PERIOD <b>1815 and later</b> STYLE <b>Federal and Victorian</b> ARCHITECT BUILDER  3. FOR LIBRARY OF CONGRESS USE	
4. NOTABLE FEATURES, HISTORICAL SIGNIFICANCE AND DESCRIPTION <div style="text-align: right;">OPEN TO PUBLIC <b>yes</b></div> <p>The old Brick Hotel was originally a federal structure 7 bays long and probably 3 or 4 deep built about 1815. The 2nd storey front of the building still contains the odd 6/6 windows with the flat white double keystone arches. The inn was later enlarged and its A-roof changed to a Mansard one. Finally in the 1920's it reached its present size of 7 bays wide and 8 bays deep with a Mansard roof capping all.</p> <p>Today it stands a much-altered though very pleasing commercial block. All of the shopfronts are in keeping with the character of the building and the soft green trim contrasts very well with the hues of the brick. Historically important as one of the oldest inns in Easton, this commercial block in its present state harmonizes with the best of the architecture in the town. The commercial enterprises housed within in no way mar the appearance of the building.</p>			
5. PHYSICAL CONDITION OF STRUCTURE    Endangered    Interior <b>well-maintained</b> <div style="text-align: right;">Exterior</div>			
6. LOCATION MAP (Plan Optional)  		7. PHOTOGRAPH  	
8. PUBLISHED SOURCES (Author, Title, Pages) INTERVIEWS, RECORDS, PHOTOS, ETC.		9. NAME, ADDRESS AND TITLE OF RECORDER  <b>Paul A. Brinkman</b>  DATE OF RECORD <b>30/8/1967</b>	



T-26  
Stewart Building  
(Old Brick Hotel)  
101-105 North Washington Street, and 10 Federal St.


EASTON  
HISTORIC  
DISTRICT  
T-410

Scale - 15 Rods to an inch

445  
447  
449  
451  
453  
455  
457  
459  
461  
463  
465  
467  
469  
471  
473  
475  
477  
479  
481  
483  
485  
487  
489  
491  
493  
495  
497  
499  
501  
503  
505  
507  
509  
511  
513  
515  
517  
519  
521  
523  
525  
527  
529  
531  
533  
535  
537  
539  
541  
543  
545  
547  
549  
551  
553  
555  
557  
559  
561  
563  
565  
567  
569  
571  
573  
575  
577  
579  
581  
583  
585  
587  
589  
591  
593  
595  
597  
599  
601  
603  
605  
607  
609  
611  
613  
615  
617  
619  
621  
623  
625  
627  
629  
631  
633  
635  
637  
639  
641  
643  
645  
647  
649  
651  
653  
655  
657  
659  
661  
663  
665  
667  
669  
671  
673  
675  
677  
679  
681  
683  
685  
687  
689  
691  
693  
695  
697  
699  
701  
703  
705  
707  
709  
711  
713  
715  
717  
719  
721  
723  
725  
727  
729  
731  
733  
735  
737  
739  
741  
743  
745  
747  
749  
751  
753  
755  
757  
759  
761  
763  
765  
767  
769  
771  
773  
775  
777  
779  
781  
783  
785  
787  
789  
791  
793  
795  
797  
799  
801  
803  
805  
807  
809  
811  
813  
815  
817  
819  
821  
823  
825  
827  
829  
831  
833  
835  
837  
839  
841  
843  
845  
847  
849  
851  
853  
855  
857  
859  
861  
863  
865  
867  
869  
871  
873  
875  
877  
879  
881  
883  
885  
887  
889  
891  
893  
895  
897  
899  
901  
903  
905  
907  
909  
911  
913  
915  
917  
919  
921  
923  
925  
927  
929  
931  
933  
935  
937  
939  
941  
943  
945  
947  
949  
951  
953  
955  
957  
959  
961  
963  
965  
967  
969  
971  
973  
975  
977  
979  
981  
983  
985  
987  
989  
991  
993  
995  
997  
999

U.D.T-410-3 EASTON

Talbot Co.



T-26  
Stewart Building (Old Brick Hotel)  
101-105 N. Washington Street, and  
10 Federal Street  
Easton Quad, 1942, PR 1974

AIRPORT

T-26

St Aubins  
Heights


EASTON  
(BM 38)

RIVER

EDMUNDSON

NECK

(TRAPPE)  
5761 II NE  
SCALE 1:24,000





11 x 2.04

73% 26

Stewart Building (Cold Brick Hotel)

100-105 N. Washington Street  
and

10 Federal Street, Easton

Southeast Facade

26





STEWART BUILDING

" OLD BRICK HOTEL "

T-216

NORTH WASHINGTON

EASTON, MD.

SOUTH & EAST FACADES

M.L. FRITZ

8/76



T-26

Stewart Building (Old Brick Hotel)

104-105 N. Washington Street & 10 Federal Street,  
Southeast Facade Easton